



The Double Auger equipment is specially designed to provide basement walls close to existing structures and maximising the available basement space. The single action of providing one wall without the need for underpinning makes it extremely cost effective and can provide time savings to the project as excavation is continuous with the frames being installed as the excavation deepens.



Project
 22, Quington Square, London
 Hard Hard Secant Basement Piled Walls

Title
 Sketch of construction sequence for the installation of a Secant concrete piled wall through the existing foundations.